

Advantages of a



- Structural Calculations for 10 tonne per axle in normal ground conditions, site specific when required, up to 50 tonne.
- Jacking rail 150 x 75 PFC
- Zone 2 lights – Flameproof twin tubed
- Premier Safety Lights (Epsilon 05 Atex 1426 X)
- Armoured steel cable with zoned glands
- Lights and cables attached to galvanised unistrut with a plastic fascia
- Anti-slip steps, Elephant tread – Galvanised.
- Handrail – Hinged or fixed
- Galvanised step-up rail for aluminum step up platform to run on
- Integral sump fitted as standard, no pump.
- Unique bond of steel to concrete – Solid. Pecafil girder, not sprags.
- 10 year warranty on Premier Pits installation
- First pit installed 35 years ago and still in daily use
- All pits sand blasted to SA 2 1/2, Etch Primer 10 – 20 microns.
- Top coat – ISO free 2 pack modified epoxy 180 micro DFT.
- All employees on PAYE

Please note that not all prefabricated pits are to this standard